

Speed Post

**ARYABHATTA RESEARCH INSTITUTE OF OBSERVATIONAL SCIENCES (ARIES),
MANORA PEAK, NAINITAL-263 129 (INDIA)**

Phone (91-05942) 233727,233734,233735,232655, Fax No. (91-05942) 233439, Gram: ASTRONOMY

AO/595/13-19(3)/09-10

Dated: 27 May, 2010

Short Tender Notice

Director ARIES invites sealed tenders in two bid system (technical bid & commercial bid) to supply and installation of Submersible Pump at Devasthal ARIES Premises, Nainital by 8.06.2010 up to 2:00 P.M. The technical bid & commercial bid are submitted in a separate sealed envelop and both should be put up in an another envelop and **it should be superscribed as "tender for Submersible Pump."** The bids should be sent through courier/speed post, the bids shall be opened on the same day at 3:30 P.M. by the purchase committee.

SI. No	Description of work	Specification	Estimated Cost	Duration of work completion	Validity of tender	EMD
1	supply and installation of Submersible Pump at Devasthal, ARIES Premises with on site warranty offered by OEM	Asper attached sheet	Rs.93,700.00	15 days	15 days	NIL

The tender bid can be cancelled without assigning any reason whatsoever by the Director ARIES.


(Indranil Chattopadhyay)
Chairman Purchase Committee

1. Supply, installation, testing & commissioning of 15 HP submersible pump set of 'Varuna' make model No. VSS60H, 15.H.P. stage 24, 3 phase 415V, 50 Hz operated Total head 380M with 3 meter double cable submersible pump set discharge 180 LPM at 380M Head complete as per manufacturer's specification & as directed. 1 No.
2. Supply & fixing of 4 sqmm L&T make 3 core copper ~~core~~ conductor submersible cable. 200 RM
3. Supply & fixing of L&T make control panel suitable for 15 HP submersible pump set with Star/Delta starter, Amperes meter & Volt meter and single phase protector etc. complete as directed. 1 No.
4. Supply & fixing of automatic water level controller 'Varuna' make or as approved without cable cost etc. complete as directed. 1 No.
5. Supply & fixing of water level control cable wire as per manufacturer's specification etc. complete. 200 RM

